

15-033-20017-0000

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Intent to Drill,  
filed October 12, 1967.

RECEIVED  
OCT 20 1967  
10-20-67  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name J. M. Huber Corporation  
Complete Address: 5415 Pennsylvania, Oklahoma City, Oklahoma 73100  
Lease Name Einsel-Biddle Well No. # 3  
Location C SW Sec. 13 Twp. 33 Rge. 17 (E) (W) W  
County Gomanche Total Depth 5165'  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X  
Other well as hereafter indicated: \_\_\_\_\_  
Plugging Contractor: Leben Drilling, Inc.  
Address: 815 Wichita Plaza Bldg., Wichita, Ks. 67202 License No. \_\_\_\_\_  
Operation Completed: Hour 3:30PM Day 29th Month October Year 1967

The Above well was plugged as follows:

412' of 8 5/8" surface pipe, cement circulated with 400 sacks. Fluid level  
in the hole was at 300', 1st cementing plug, bridged with 1/2 sack of hulls  
on fluid at 300', and cemented with 25 sacks, with cement from 290' to 215'.  
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged with 1/2  
sack of hulls on fluid at 40', and cemented with 10 sacks, with cement from  
30' to the base of the cellar. Rat and mouse holes bridged and cemented with  
4 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Audie Elving  
Well Plugging Supervisor

INVOICED

DATE 10/30/67  
INV. NO. 6574-W