

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued August 11, 1967.

RECEIVED
STATE CORPORATION COMMISSION
AUG 14 1967
8-14-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Roy D. McAninch
Complete Address 1363 First National Bldg., Oklahoma City, Oklahoma 73102
Lease Name Oller Well No. # 1
Location SW SE Sec. 33 Twp. 34 Rge. 16 (E) (W) W
County Comanche Total Depth 5260'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Clarke Corporation, Inc.
Address Chapin Bldg., Medicine Lodge, Kansas License No. 583
Operation Completed: Hour 12:30 P.M. Day 10th Month August Year 1967

The above well was plugged as follows:

345' of 13 3/8" surface pipe, cement circulated. 5259' of 5 1/2" long string,
cemented with 100 sacks. Top perforation 5220'. Bottom of the hole was sanded
to 5150', and cemented with 5 sacks, through the dump bailer, with cement from
5150' to 5110'. 4371' of 5 1/2" long string was recovered from the hole. Fluid
in the hole was bailed down to 300', bridge plug and rock bridge from 300' to
290', and cemented with 50 sacks, with cement from 290' to 230'. Hole was
filled with mud to 40', rock bridge from 40' to 30', and cemented with 25
sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 8/14/67

INV. NO. 6128-W