

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-033-20330-0000 (of this well)

Operator's Full Name Mid-Continent Energy Corp.

Complete Address 120 S. Market, Suite 712, Wichita, Ks. 67202

Lease Name Merrill Ranch Well No. 2

Location 150' N/C NW NE Sec. 14 Twp 34s Rge. 16 (E) (W) X

County Comanche Total Depth 5004

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A _____

Other ~~well~~ ~~as hereafter indicated~~ The Intent showed 4973' should be 5004'

Plugging Contractor Kelso Casing Pulling.

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 4 Pm. Day 20 Month 3 Year 1980

The above well was plugged as follows:

280' 13 3/8" casing w/300 sax cement. 1011' 8 5/8" casing w/1100 sax
cement. 998' 7" casing w/100 sax cement. 4 1/2" casing set at 5004'-
w/100 sax cement. Plug back to 4696'-Preforated at 4661' to 4665'-
Sand back to 4625'-Top sand w/ 4 sax mixed cement w/ dump bailer.
Pull 4220' casing. Set rock bridge at 660'-Hildinger dumped 5 yard
grout in 7" casing to top of casing.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 3-24-80

INV. NO. 1786-w

MAR 24 1980
3-24-80
CONSERVATION DIVISION
Wichita, Kansas