

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -033-20329-0000 (of this well)

Operator's Full Name Mid-Continent Energy Corp.

Complete Address 712 One Twenty Bldg., Wichita, Ks. 67202

Lease Name Merrill Ranch Well No. 1

Location C NE SW Sec. 15 Twp. 34s Rge. 16 (E) (W) X

County Comanche Total Depth 5290

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling.

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 2:30 Pm Day 28 Month 2 Year 1980

The above well was plugged as follows:

281' 13 3/8" casing. 4 1/2" casing set at 5207' w/150 sax cement.
Plug back to 5165'-Preforated at 5114' to 5118'-Sand back to 5075'-
Top sand w/4 sax mixed cement w/dump-bailer. Pull 3795' 4 1/2"
casing. Allied mixed & pumped 10 sax hulls-24 sax gel-225 sax 50/50
posmix cement w/4% gel to top of casing. Shut in w/200# pressure.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION

Signed: [Signature]
Well Plugging Supervisor

INVOICED 3-3-80
MAR 3 1980

DATE 3-3-80
CONSERVATION DIVISION
W. NO. [initials]