

State of Kansas



15-033-20017-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY	Governor
WILLIAM L. MITCHELL	Chairman
JAMES O. GREENLEAF	Commissioner
HARRY G. WILES	Commissioner
RAYMOND B. HARVEY	Secretary
E. EDWARD JOHNSON	Gen. Counsel

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 20 1967
16-70-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed October 12, 1967.

Dear Sir:

Mr. Troy Downey of J. M. Huber Corporation has this date requested permission to plug the following described well:

Mr. Downey guarantees payment of the plugging fee.

Operator's full Name: J. M. Huber Corporation

Complete Address: 5415 Pennsylvania, Oklahoma City, Oklahoma 73100

Lease Name: Einsel-Biddle Well No. # 3

Location: C SW Sec. 13 Twp. 33 Rge. 17(E)(W) W

County Kiowa COMANCHE Total Depth 5165' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Downey was instructed to plug the well as follows:

412' of 8 5/8" surface pipe, cement circulated with 400 sacks. Fill
hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge rat & Mouse holes with 4 sacks
and cement

Very truly yours,

Archie Elving
 Conservation Division Agent