



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

DEC 9 1963
 12-9-63
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Jack Joener of Petroleum Management Inc. has this date requested permission to plug the following described well:

Mr. Joener guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management Inc.

Complete Address: 1515 Wichita Plaza, Wichita, Kansas

Lease Name: Warren Ranch Well No. # 1

Location: SE SE Sec. 35 Twp. 33 Rge. 17 (E) (W) W

County Comanche Total Depth 5776 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Joener was instructed to plug the well as follows:

319' of 13 3/8" surface pipe, cemented with 450 sacks.
Fill hole with drilling mud to 275', 1st cementing plug,
bridge with hulls, cement with 35 sacks. Fill hole with
drilling mud to 40', 2nd cementing plug, bridge with hulls,
cement with 20 sacks to base cellar. Bridge mouse and rat
holes and cement with 4 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent