



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

22 February 1982

RECEIVED
STATE CORPORATION COMMISSION

MAR 2 - 1982
3-2-82
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-033-20523 - 0000

Dear Sir:

Mr. Butch Steinert of Eagle Drilling Co., Inc. ^{Rig #1} has this date requested permission to plug the following described well:

Operator's Full Name: Scandia Resources Inc., % Gould Oil Inc.

Complete Address: P.O. Box 8640 Wichita, Kansas

Lease Name: Bannick Well No. 1-33

Location: 1780' FNL-2080' FNL Sec. 33 Twp. 34 Rge. 16W (E) (W)

County: Comanche Total Depth: 5320'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Steinert was instructed to plug the well as follows:

1st plug 980' with 50 sbp of cement. The surface casing was at 421' of 8 3/4" cement circulated with 400 lbs of cement. 2nd plug pushed rubber plug to 400' and pumped 35 sbp on top of it. 3rd plug 40' to 0' on solid bridge with 10 sbp of cement. Then circulated 10 lbs of cement in rat hole + 5 sbp ^{Cement} in mouse hole. The cementing was pumped through drill pipe with hole full of heavy mud. The plugging was accomplished by Allied Cementing

Very truly yours,

Paul Luthi
Conservation Division Agent