

15-033-00066-0000

FALCON SEABOARD DRILLING COMPANY
 BALLETT NO. I WELL
 SW SW Sec. 36-34S-16S
 COMANCHE COUNTY, KANS.
 DRILLER'S LOG

Commenced Drilling 3/25/48
 Completed Drilling 5/10/48
 Set - 1116' - 8-5/8" Surface Casing
 Cemented W/500 Skts.
 Plugged D & A - 5/10/48

Surface Clay - Red Bed	0	60	Shale & Chert	4770	4823
Red Shale	60	125	Shale & Lime Broken	4823	4856
Red Bed	125	500	Shale & Lime	4856	4931
Gypsum	500	540	Shale & Shells	4931	4954
Red Bed & Shells	540	573	Shale & Lime	4954	5060
Red Bed & Gypsum	573	973	Lime	5060	5067
Shale & Gypsum	973	1029	Lime & Shale	5067	5160
Blue Shale	1029	1115	Lime & Chert	5160	5182
Green Shale	1115	1130	Chert	5182	5183
Shale & Shells	1130	2100	Lime & Shale (Cherty)	5183	5188
Lime & Shale	2100	2232	Shale & Lime	5188	5216
Shale & Shells	2232	2305	Shale & Chert	5216	5237
Shale & Lime	2305	2320	Lime	5237	5250
Lime	2320	2347	Brown Lime	5250	5277
Shale & Lime	2347	2375	Shale & Lime	5277	5301
Lime (Chert)	2375	2429	Shale	5301	5317
Shale & Lime	2429	2490	Shale & Lime (Cherty)	5317	5343
Lime & Chert & Chert Strks	2490	2505	Shale & Lime	5343	5380
Shale	2505	2520	Lime	5380	5403
Shale & Shells	2520	2538	Shale & Lime	5403	5460
Shale & Lime	2538	2625	Shale	5460	5486
Shale & Chert	2625	2655	Shale & Lime	5486	5500
Shale & Shells	2655	2745	Shale	5500	5540
Shale & Lime	2745	2895	Lime	5540	5608
Shale & Shells	2895	3077	Chert	5608	5613
Shale & Lime	3077	3593	Lime	5613	5616
Shale & Shells	3593	3645	Chert	5616	5622
Lime & Shale	3645	3814	Lime & Chert	5622	5644
Broken Lime	3814	3840	Lime	5644	5656
Lime	3840	3900	Lime & Chert	5656	5677
Lime & Shale	3900	3920	Lime	5677	5706
Shale	3920	4190	Lime & Chert	5706	5726
Lime & Shale	4190	4215	Lime	5726	5745
Shale & Shells	4215	4378	Dolomite	5745	5756
Shale	4278	4404	SP Dolomite	5756	5785
Shale & Lime	4404	4472	Sand (Simpson)	5785	5787
Lime & Chert	4472	4497	Shale & Dolomite	5787	5795
Shale & Lime	4497	4539	Shale & Sand	5795	5819
Lime	4539	4655	Shale	5819	5895
Lime & Chert	4655	4676	Shale & Sand	5895	5914
Lime	4676	4715	Lime	5914	5917
Lime & Chert	4715	4751	Shale	5917	5933
Lime & Shale	4751	4764	Sandy Shale	5933	5953
Lime	4764	4770	Lime	5953	5986
				TOTAL DEPTH	5986

I hereby certify that the foregoing is a true and correct copy of the Ballett No. 1 Well Driller's Log as it is recorded on the log books of the Falcon Seaboard Drilling Company.

J. O. Brown
 J. O. Brown

STATE OF OKLAHOMA)
 COUNTY OF TULSA) SS

Subscribed and sworn to before me this 12th day of May, 1948.

Galves Walsh
 Notary Public

My Comm. Expires:
 Feb. 8, 1950

