


15-033-20065-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD



Comanche County, Sec. 16 Twp. 34S Rge. (E) 17 (W)
Location as "NE/CNW%SW%" or footage from lines 1110' FSL & 1070' FEL
Lease Owner Yucca Petroleum Co.
Lease Name GUSS Well No. 1
Office Address P.O. Box 2585, Amarillo, Texas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 7, 19 70
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced June 7, 19 70
Plugging completed June 7, 19 70
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well B. R. Biberstein of Attica, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 6125 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Casing	0	397'	8-5/8"	397'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.


50 sax Cement from 6050 Feet to 5830 Feet;
Heavy Mud to 500 Feet; 60 sax Cement to
300 Feet; Mud to 40 Feet, 1/2 sax Halls,
Plug Bridged w/Kelly & 10 sax Cement to
Base of Cellar; 2 sax Cement in Rat Hole.
Job Completed @ 4:15 A.M. on 6/7/70.

RECEIVED
STATE CORPORATION COMMISSION
6-15-70
JUN 15 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sage Drilling Co., Inc.
Address 500 Bitting Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
T. M. McCaul, Jr. of Sage Drilling (employer of owner) (operator) of the above described well being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. M. McCaul, Jr.
500 Bitting Building, Wichita, Kansas
(Address)



Subscribed and Sworn to before me this 12th day of June, 19 70
Louise K. Whitted
Louise K. Whitted - Notary Public.

November 26, 1970

DRILLERS LOG

GUSS NO. 1

CASING RECORD:	OPERATOR:	Yucca Petroleum Co.	DESCRIPTION:
8-5/8" @ 397' w/250 sax cement	CONTRACTOR:	Sage Drilling Co., Inc.	1110'FSL & 1070'FEL Sec. 16-34S-17W Comanche Co., Kansas
TOTAL DEPTH:	COMMENCED:	May 21, 1970	ELEVATION: 1764 KB
6125'	COMPLETED:	June 7, 1970	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Red Bed & Sand	0	215	
Red Bed, Shale & Shells	215	630	
Shells & Shale	630	1059	
Red Bed & Shale	1059	1695	
Shale & Shells	1695	2095	
Shale, Shells & Lime	2095	2192	
Lime & Shale	2192	2905	
Shale & Lime	2905	3705	
Sandy Shale	3705	3985	
Lime & Shale	3985	4115	
Lime	4115	4330	
Shale & Lime	4330	4400	
Lime	4400	4990	
Lime & Chert	4990	5010	
Lime, Shale & Sand	5010	5084	
Lime	5084	5181	
Mississippi	5181	5625	
Lime	5625	5803	
Lime & Chert	5803	5910	
Lime, Chert & Sandy Lime	5910	5970	
Sandy Lime & Chert	5970	6008	
Lime & Chert	6008	6066	
Cherty Lime, Shale & Arbuckle	6066	6125	D&A

RECEIVED
STATE CORPORATION COMMISSION
6-15-70
JUN 15 1970
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By T. M. McCaul, Jr.
T. M. McCaul, Jr.



Subscribed and sworn to before me this 12th day of June, 1970.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1970.