

RECEIVED
9-22-03
SEP 22 2003
KCC WICHITA

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-033-21364-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date. *2/04*

WELL OPERATOR Guardian Energy Consultants, Inc. KCC LICENSE # 32786
(owner/company name) (operator's)

ADDRESS 403 S. Cheyenne #403 CITY Tulsa

STATE Oklahoma ZIP CODE 74103 CONTACT PHONE # (918) 599-9327

LEASE Arena WELL# 1 SEC. 5 T. 34 R. 117 (~~East~~/West)

SE - NW - SW - SPOT LOCATION/QQQQ COUNTY Comanche County, Kansas

1520 FEET (in exact footage) FROM S (circle one) LINE OF SECTION (NOT Lease Line)

1220 FEET (in exact footage) FROM E (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE 20" SET AT 45' CEMENTED WITH SACKS

SURFACE CASING SIZE 10-3/4" SET AT 347' CEMENTED WITH 625 SACKS

PRODUCTION CASING SIZE SET AT CEMENTED WITH SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:

ELEVATION 1845/1856' T.D. 5960' PBD ANHYDRITE DEPTH
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Spot 50 SK plug @ 800' Through Drill Pipe, Spot 75 SK Plug @ 380' Through Drill Pipe, Spot 20 SK Plug @ 40' Through Drill Pipe, Fill Rat Hole with 15 SK, Fill Mouse Hole with 10 SK.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Guardian Energy Consultants, Inc. PHONE# 918 599-9327

ADDRESS 403 S. Cheyenne, #403 city/state Tulsa, OK 74103

PLUGGING CONTRACTOR Duke Drilling Co., Inc. KCC LICENSE # 5929
(company name) (contractor's)

ADDRESS PO Box 823 Great Bend, KS 67530 PHONE # (316) 267-1331

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 08-27-03 4:30 AM Plugged

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 9-19-03 AUTHORIZED OPERATOR/AGENT: David W. French
(signature)