

15-033-00005-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Comanche County. Sec. 18 Twp. 34 Rge. 16 (E) (W)

Location as "NE/CNW/SW" or footage from lines Center SE SE

Lease Owner Sun Oil Company, et al

Lease Name Gates Ranch Unit Well No. 1

Office Address Box 1348, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7-30- 1955

Application for plugging filed 8-8- 1955

Application for plugging approved 8-8- 1955

Plugging commenced 8-11- 1955

Plugging completed 8-14- 1955

Reason for abandonment of well or producing formation Recovered small show oil and considerable salt water

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Pratt, Kansas

Producing formation None Depth to top Bottom Total Depth of Well 6100 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Miss. Chat	Sho oil & wtr	5097	5110	13-3/8"	310.94'	None
Miss. Lime	salt water	5176	5198	8-5/8"	2334'	None
Miss. Lime	salt water	5260	5276	5 1/2"	5355.45'	1600'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with pea gravel from PBTD 5245'-5080'. Drove wooden plug to 4850'. Plugged back with crushed rock from 4850'-4840'. Spotted 5 sax cement with dump bailer at 4801'-4840'. Pulled 5 1/2" casing. With bottom of 5 1/2" at 1600', circulated hole with heavy drilling mud. Pulled 5 1/2" out of hole. Bailed mud down to 450'. Drove wooden plug to 450'. Plugged back with crushed rock from 450'-440'. Dumped 20 sax cement from 440'-380'. Filled surface pipe with heavy mud to 35'. Drove wooden plug to 35'. Plugged back with crushed rock from 35'-30'. Dumped 10 sax cement in surface pipe, filling from 30' to top of pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company, Inc.

Address Chase, Kansas

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

J. H. Allen (Employer or Owner) or (Agent or Operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

J. H. Allen

Box 1348, Tulsa, Okla.

(Address)

SUBSCRIBED AND SWORN TO before me this 22 day of August 1955

[Signature]

Notary Public.

My commission expires 5-9-59

24-7368-S 3-53-20M

PLUGGING
WEL SEC 18 T 34 R 16 W
BOOK PAGE 141 LINE 24

RECEIVED
STATE CORPORATION COMMISSION
AUG 23 1955
8-23-55
CONSERVATION DIVISION
Wichita, Kansas

D R I L L E R ' S L O G

SUN OIL COMPANY

GATES RANCH UNIT NO. 1

SE/4 SE/4

Section 18-34S-16W

Comanche County, Kansas

Elev. D. F.
" Grd.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Surf. clay & shells	0	78
Gyp rock	78	88
Red beds and shale	88	820
shaly lime	820	1065
shale & shells	1065	1613
anhydrite & salt	1613	2305
dolo. and lime	2305	2398
shale and ls.	2398	2602
lmy. shale	2602	2893
ls. and shale	2893	3118
shaly ls.	3118	3400
ls. w/shl. strks.	3400	3798
lmy. shale	3798	4013
Elgin Sand	4013	4125
Broken shale & ls.	4125	4260
lmy. shale	4260	4392
(Lansing) ls. w/shl. streaks	4392	4790
shly. ls.	4790	5099
Miss. chat	5099	5111
Miss. lime	5111	5654
Chatt. shale	5654	5664
Viola Ls.	5664	5834
Simpson Form.		
Ls.	5834	5854
shale	5854	5878
sd.	5878	5898
sd. shale	5898	5985
Arbuckle, bro. ls. and shale	5985	6100 - T. D.

Drlg. Comm. 5-13-55
Drlg. Comp.. 7- 1-55
Casing Record:

13-3/8" at 310.94' w/300 sks. Cem.
8-5/8" at 2334' w/1100 sks. Cem.
5-1/2" at 5355.45' w/350 sks. Cem.

Perf. Record:

5097-5110 - Miss. Chat (show gas, oil and salt water)
5176-5198 - Miss. Ls. (salt water)
5260-5276 - Miss. Ls. (salt water)

D & A.

I hereby certify the foregoing is a true and correct copy of the Gates Ranch Unit Well #1 log as recorded on the books of Sun Oil Company.

J. Allen

Subscribed and sworn to before me this 5th day of August, 1955.

Blumenfeld
Notary Public

My commission expires May 9, 1959.

RECEIVED
STATE CORPORATION COMMISSION
8-10-55
AUG 10 1955
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
WEL SEC 18 T 34 R 16W
BOOK PAGE 141 LINE 24