

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
APR 15 1963  
4-15-63  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Braden Drilling Inc.

Complete Address: 1206 Union National Bldg., Wichita, Kansas

Lease Name Hadley Well No. # 1

Location C SE SE Sec. 7 Twp. 34 Rge. 17 (E) (W) W

County Comanche Total Depth 5900

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Braden Drilling Inc.

Address: 1206 Union National Bldg., Wichita, Kansas License No.     

Operation Completed: Hour 8:30PM Day 9th Month April Year 1963

The Above well was plugged as follows:

400' of 8 5/8" surface pipe cemented with 300 sacks and circulated.

Hole was filled to 240' with mud, 1st cementing plug, 1/2 sack hulls,

cemented with 20 sacks. Hole filled to 40' with mud, 2nd cementing

plug, 1/2 sack hulls, cemented with 10 sacks to base cellar. Rat and

mouse hole bridged and cemented with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 4/15/63  
INV. NO. 6904-W

Signed: Archie Elving  
Well Plugging Supervisor