

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

15-033-01002-00-07

API Number 15- _____

(none)

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Union Oil Co. of California

Complete Address 2000 Classen Center, South Bldg, Oklahoma City, Okla 73106

Lease Name Hazel Beals Well No. 1

Location C-NE-SW Sec. 5 Twp. 34 Rge. 17W (East)(West)

County Comanche Total Depth 5940'

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Lillard Casing Pullers Inc.

Address 3022 N. W Expressway Suite 417 Oklahoma City Okla 73102 License No. 618

Operation Completed: Hour: 7:00 PM Day: 22 Month: January Year: 19 82

Plugging Operations attended by Agent?: All Part _____ None _____

The above well was plugged as follows:

There is 246' of 13 3/8" conductor pipe cement circulated. The perforations were at 4393' to 4576'. They ran 5799' of 5 1/2" production pipe, cement was at 4000' out side of pipe. The perforations were at 4393' to 4576'. They plugged back to 4830'. 1st plug pumped 1 skb of hulls + 35 skb of cement to bottom of hole. 2nd plug at 2645' with 50 skb of cement. 3rd plug 40' to 0' with 10 skb of cement. They recovered 3510' of production pipe. The plugging was accomplished by Lillard casing pullers Inc.

Amount of Surface Casing: 2592' of 8 3/8" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul Luther
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

INVOICED
DATE 1-26-82
INV. NO. 9127W

Signed: _____ RECEIVED
Conservation Division Agent

JAN 26 1982
1-26-82
CONSERVATION DIVISION
Wichita Kansas