

K
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

FEB 8 1963
2-8-63
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name L. B. Jackson Drilling Co.

Complete Address: 503 Mayo Bldg., Tulsa, Oklahoma

Lease Name Petro Well No. # 1

Location C SE NW NW Sec. 7 Twp. 34 Rge. 19 (E) (W) W

County Comanche Total Depth 6313

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Co.

Address: P. O. Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 10:AM Day 5th Month Feb. Year 1963

The Above well was plugged as follows:

Hole was originally drilled to 6313' and plugged back.
5654' of 5 1/2" long string. Plugged back to 5245'. Top of perferation
5200'. Sanded to 5180' cemented with 5 sacks. 369' of 8 5/8" surface
pipe circulated with cement. Hole was filled to 200' and a 10' rock
Bridge cemented with 20 sacks. Hole was filled with mud to 40' and
a 10' rock bridge cemented with 10 sacks to base cellar
4312' of pipe recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2-8-63

INV. NO. 6542-W