

15-167-08053-00-00

R CP3

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 143-16

LOCATION NE-7W-SE

Cable Tool Hole

SEC. 4 TWP. 14 RGE. 15

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 5 Lease A. K. Witt

Operator Margaretta Billings Address Box # 272 - Russell-Kans.

Field _____ County Russell-Kans.

Total Depth 3087 Feet.

(Describe briefly the manner in which the well was plugged)

10 3/4 casing at 822 ft. Not cemented
6" casing at 3021 ft. 50 sacks of cement -
10 3/4 x 6" casing cemented & rammed together
from 400 ft to the surface. Plugged back to 2940 ft
with sand. Dumped 15 sacks of cement at 2940 ft.
26" casing pulled. Litter hole with mud from
bottom to 250 ft. Set each bridge & 20 sacks of cement
at 250 ft. rammed to 35 ft. Plug 6" sacks of cement at
the surface.

Barns & Sons - Plugging Contractors

RECEIVED

STATE CORPORATION COMMISSION

PLUGGING

FILE SEC 4 T 14 R 15 MAY 24 1952

BOOK PAGE 143 LINE 24 CONSERVATION DIVISION

Wichita, Kansas

C. H. Stough
District Conservation Agent

Date 5-19-52