

1052385

TO: STATE CORPORATION COMMISSION

API NUMBER 15-033-21,075-0000
APP. N/2 SW NW SEC. 13, T 34 S, R 17 W

CONSERVATION DIVISION - PLUGGING SECTION 1667 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 760 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME CORBETT-GATES WELL # 13-5

TECHNICIAN'S PLUGGING REPORT

COUNTY COMANCHE 185.25

OPERATOR LICENSE # 32389 5/1

WELL TOTAL DEPTH 5700 FEET

OPERATOR: STAR RESOURCES, LLC

PRODUCTION CSG: SIZE @ WITH SX

NAME AND PO BOX 5185

SURFACE CASING: SIZE 8 5/8" @ 724' WITH SX

ADDRESS ENGLEWOOD, CO 80155

CONDUCTOR CSG: SIZE @

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR VAL ENERGY

LICENSE NUMBER 5822

ADDRESS PO BOX 116 WICHITA, KS 67201

COMPANY TO PLUG AT: HOUR: 3:30 AM DAY: 01 MONTH: 05 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM SKIP

(COMPANY NAME) VAL ENERGY (PHONE) 316-263-6688

WERE:

1ST PLUG AT 760' WITH 50 SX CEMENT. 2ND PLUG AT 300' WITH 40 SX CEMENT.

3RD PLUG AT 40' WITH 10 SX CEMENT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 6:30 AM DAY: 01 MONTH: 05 YEAR: 2000

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 760' WITH 50 SX CEMENT. 2ND PLUG AT 300' WITH 40 SX CEMENT.

3RD PLUG AT 40' WITH 10 SX CEMENT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID NOT) OBSERVE THIS PLUGGING.

SIGNED

Richard W. Lacey
(TECHNICIAN)

FORM CP-2/3

INVOICED RECEIVED
STATE CORPORATION COMMISSION

DATE 5/9/00

MAY 4 2000

5-4-00

CONSERVATION DIVISION
Wichita, Kansas

R