

1-060297

15-033-20633-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Not available  
NE SW, SEC. 8, T 34 S, R 19 W/E  
1980 feet from ~~XXX~~ section line  
3300 feet from ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5673

Lease Name Harbaugh Well # 1

Operator: W. L. Kirkman  
Name & Address: 453 South Webb Road, Suite 100  
Box 18611  
Wichita, KS 67207

County Comanche  
Well Total Depth 5378 174.79 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 686

Abandoned Oil Well XX Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ S&D Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 8 Month: August Year: 19 84

Plugging proposal received from Clay Duntz

(company name) Kelso (phone) 316-938-2456

were: PBD 5351 4 1/2" set at 5370' Perfs 5235-39'

1st plug pump 30 sx cement to bottom

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release  
8 5/8" rubber plug and pump an additional 150 sx cement

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:10 pm Day: 8 Month: August Year: 19 84

ACTUAL PLUGGING REPORT PBD 5351' 4 1/2" set at 5370' Perfs 5235-39'

1st plug pumped 30 sx cement to bottom, 2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx  
cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx  
cement.

Maximum pressure 550 psi and shut in pressure 400 psi

Remarks: They recovered 3334' of 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Sun  
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-16-84  
INV. NO. 3209 8-8

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 16 1984  
8-16-84  
CONSERVATION DIVISION  
Wichita, Kansas

Signed Paul A. Luthi  
(TECHNICIAN)