

1 090020

8-28

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-033-20,585-0000
C. NE NE, SEC. 18, T. 34 S, R 19 W/E
4620 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6574

Lease Name Hackney Well # 18-1

Operator: Bird Energy Inc.
Name & Address 2020 Thompson
P.O. Box 1612
Dodge City, KS 67801

County Comanche 174.01
Well Total Depth 5354 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 766

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address 107 West Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 11 a.m. Day: 28 Month: 8 Year: 19 89

Plugging proposal received from Mark Pennick

(company name) Bird Energy Inc.

RECEIVED
STATE CORPORATION COMMISSION
(phone) 316-622-4868

were: 4 1/2" at 5353' Perfs at 4816-21, 5242-50'

AUG 31 1989
8-31-89

1st plug sand back to 4850' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 7 sx gel, 100 lbs. hulls,

release 8 5/8" wiper plug and pump 120 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 28 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4758' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 400 lbs. hulls, 10 sx gel, 50 sx cement, 7 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Maximum pressure 300 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 4012' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-6-89

Signed Michael A Wilson
(TECHNICIAN)

INV. NO. 25796

8-28