

1060515

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-033-20,307-0000
C NE NE, SEC. 19, T 34 S, R 19 W/EX

TECHNICIAN'S PLUGGING REPORT

4620 feet from S section line
660 feet from E section line

Operator License # 6780

Lease Name Lemon Well # 1

Operator: Lear Petroleum Exploration, Inc.
Name & Address 6401 NW Grand Building, # 200
Oklahoma City, OK 73116

County Comanche 172.25
Well Total Depth 5300 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 652

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address P. O. Box 506, Liberal, KS 67901

Company to plug at: Hour: 3:00 pm Day: 18 Month: March Year: 19 85

Plugging proposal received from Bob Sargent's
(company name) Sargent's (phone) 316-624-7455

were: 4 1/2" at 5299' PBD 5250' Perfs at 5188-5240
Spot plugs through 4 1/2" casing with mud between plugs
1st plug pump 1 sack hulls and 25 sx cement to bottom

2nd plug at 700' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:00 pm Day: 18 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 1 sack hulls and 25 sx cement to bottom, 2nd
plug at 700' with 50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' --
cement to surface with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 25 1985

3-25-85
CONSERVATION DIVISION

Wichita, Kansas

Remarks: Used common sacked cement by Sargent's. Recovered 3513' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-26-85

INV. NO. 7441

3-18

Signed Paul A. Luthi
(TECHNICIAN)