

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-033-20,556-0000

~~NE 1/4~~ SEC. 20, T. 34 S., R. 19 W. W

2310 FEET FROM ~~N/S~~ SECTION LINE

1650 FEET FROM ~~NE~~ SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 7007

LEASE NAME HIBBERT WELL # 4-20

OPERATOR: Bow Valley Petroleum, Inc.  
NAME & ADDRESS 1700 Broadway, Suite 900  
DENVER, CO, 80290

COUNTY COMANCHE

WELL TOTAL DEPTH 5410 \$175.83 FEET

CONDUCTOR PIPE: SIZE \_\_\_\_\_ FEET \_\_\_\_\_

SURFACE CASING: SIZE 8 5/8 FEET 610

ABANDONED OIL WELL X GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR Jerry Duncan Well Pulling LICENSE NUMBER 8733

ADDRESS 1913 N. 10th, ENID, OK, 73701

COMPANY TO PLUG AT: HOUR: 9 AM DAY: 1 MONTH: July YEAR: 19 83

PLUGGING PROPOSAL RECEIVED FROM Mike Riner

(COMPANY NAME) Bow Valley (PHONE) \_\_\_\_\_

WERE: Lay down 4 1/2" and pump 30 sy cmt. plug to 3970' (top) - Load hole w/mud - set 50 sy at 700' - set 50 sy @ 650' - 40'-0' w/10 sy

PLUGGING PROPOSAL RECEIVED BY: R. Barluttan  
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART \_\_\_\_\_ NONE \_\_\_\_\_

OPERATIONS COMPLETED: HOUR: 12:30 DAY: 1 MONTH: July YEAR: 19 83  
NOON

ACTUAL PLUGGING REPORT Plugged as proposed.  
Cementing by Jerry Duncan.

Agent observing plugging was Richard Lacey.

REMARKS: 4 1/2 @ 4960 - rec. 4010' - Perfs @ 4890' - 4896'

I ~~did~~ / DID NOT) OBSERVE THIS PLUGGING.

INVOICED

DATE 7-14-83

INV. NO. 484860

SIGNED R. Barluttan  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION

JUL 07 1983  
7-7-83  
CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
REV. 6-83

15-033-20556-0000



## Bow Valley Petroleum Inc.

1700 Broadway, Suite 900, Denver, CO 80290

April 26, 1983

Telephone: (303) 861-4366  
Telecopier: (303) 832-3825  
Telex: 45-0033

Kansas Corporation Commission  
200 Colorado Derby Building  
Wichita, Kansas 67202

Attention: Tom Lieker

Re: Hibbert #4-20

Gentlemen:

On April 22, 1983, Bow Valley Petroleum sent a well plugging application to your office. Please be informed that our plugging contractor will be Toland and Johnson, P.O. Box 94336, Oklahoma City, Oklahoma 73143; their KCC license number is #539.

The work is scheduled to begin around May 20, 1983. If you have any questions or need another application or information please advise.

Sincerely,  
Bow Valley Petroleum, Inc.

Mike Rivera  
Staff Engineer

MR/11m

cc: Toland and Johnson

RECEIVED  
STATE CORPORATION COMMISSION

APR 29 1983  
4-28-83  
CONSERVATION DIVISION  
Wichita, Kansas

HIBBERT 4-20  
Plugging Procedure  
Comanche County, Kansas

1. MIRUSU and fill casing with 10ppg lease brine.
2. POOH w/pump and rods.
3. Release tubing anchor at 4860' & POOH w/tbg.
4. Find free point and shoot off casing above top of cement @ 4300ft± POOH and lay down 4½" casing.
5. Pump 25sx cement plug (class 'G') at 4955' to 3970' (Perfs = 4890-4896).
6. Fill hole w/drilling mud to 700ft.
7. Set 40sx plug to 172ft.
8. Fill hole with mud and set 10sx surface plug. 6 feet below surface.
9. Place 5sx plug in Rat hole and a 5sx plug in Mouse hole.
10. Weld on steel cap (dryhole marker).
11. Pull anchors.
12. Remove equipment.
13. Restore location and road per landowner's requirements.

RECOMMENDED:

Mike Rivera  
Mike P. Rivera  
Staff Engineer

APPROVED:

Louise Bridges  
Louise Bridges  
Exploration Manager

APPROVED:

David A. Gomendi  
David A. Gomendi  
Manager, Drilling & Production

APPROVED:

Steve R. Gray  
Steve R. Gray  
Vice President & General Manager

RECEIVED  
STATE CORPORATION COMMISSION

APR 29 1983  
4-28-83  
CONSERVATION DIVISION  
Wichita, Kansas