

1 030173

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,489 - 0000
_____, SEC. 20, T 34 S, R. 19 W/E
660 feet from N/S section line
1980 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7007

Lease Name Lowenfeld Well # 3-20

Operator: Bow Valley Petroleum, Inc.
Name & Address 1700 Broadway, Suite 900
Denver, CO 80290

County Comanche
Well Total Depth 5440 176.80 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 619

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Jerry Dunkin Casing Pulling, Inc. License Number 8733

Address P. O. Box 389, Enid, OK 73702

Company to plug at: Hour: 1:30 pm Day: 9 Month: May Year: 19 84

Plugging proposal received from Mike Moore

(company name) Jerry Dunkin Casing Pulling (phone) 316-624-7455

were: 4 1/2 set at 5439' PBSD 5408' Perfs 5289 - 5326'

1st plug pump 25 sx cement to bottom

2nd plug at 670' with 50 sx cement

3rd plug at 320' with 40 sx cement
solid bridge

4th plug bulls - plug at 40' --- cement to surface with 10 sx cement

Plugging Proposal Received by Steve Akers
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 4:00 pm Day: 9 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 5439' PBSD 5408' Perfs 5289-5326'

1st plug pump 25 sx cement to bottom, 2nd plug at 670' with 50 sx cement, 3rd plug at 320'

with 40 sx cement, 4th & 5th plugs - solid bridge - plug at 40' --- cement to surface

with 10 sx cement.

Paul Luthi gave the orders.

Remarks: Use common sack cement, by Dunkin Casing Pulling.
(If additional description is necessary, use BACK of this form.) Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAY 11 1984
5-11-84
CONSERVATION DIVISION
Wichita, Kansas

Signed Steve Akers
(TECHNICIAN)

INVOICED
DATE 5-14-84
WV. NO. 1495
5-9

MAY 23 1984