

TO: *[Handwritten mark]*
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21063-00-00
Spot: NESW Sec/Twnshp/Rge: 32-34S-19W
2080 feet from S Section Line, 1845 feet from W Section Line
Lease/Unit Name: WOOLFOLK B Well Number: 1-32
County: COMANCHE Total Vertical Depth: 6357 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W. 93 N.
VALLEY CENTER, KS 67147

Conductor Pipe: Size 20 feet: 57 *8 206.60*
Surface Casing: Size 8.625 feet: 629 WITH 425 SX CMT
Production: Size 4.5 feet: 5967 WITH 200 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 10/19/2001 2:10 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: ALAN VRATIL Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SET CIBP @ 5175'. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10S X GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/19/2001 2:45 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 5600'. PERFS AT 5420-86, 5288-5350, 5127-67'. CIBP @ 5000' WITH 2 SX CMT ON TOP. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN PRESSURE 300#.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 4000' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed *[Signature]*

(TECHNICIAN)

OCT 22 2001

RECEIVED

OCT 25 2001
10-25-01
KCC WICHITA

INVOICED

DATE

10-26-01

INV. NO.

2002060851

Form *[Handwritten mark]*