

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-20417-00-01
Spot: CNENE Sec/Twnshp/Rge: 30-34S-19W
660 feet from N Section Line, 660 feet from E Section Line
Lease/Unit Name: WEBSTER A Well Number: 1
County: COMANCHE Total Vertical Depth: 5400 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W. 93 N.
VALLEY CENTER, KS 67147

Conductor Pipe: Size feet: 8 1/2 175.50
Surface Casing: Size 8.625 feet: 329 WITH 200 SX CMT
Production: Size 4.5 feet: 5369 WITH 350 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 10/19/2001 9:30 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: ALAN VRATIL Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SET CIBP @ 3100'. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/19/2001 10:15 AM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:


PBTD 5010'. PERFS AT 3160-65'. SET CIBP @ 3080' WITH 2 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN PRESSURE 300#.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2800' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)



RECEIVED

OCT 25 2001
10-25-01
KCC WICHITA

INVOICED

OCT 22 2001

Form CP-2/3

DATE 10-26-01
2002060851

MP