

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-073-01773-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 7-22S-11E
2970 feet from S Section Line, 4950 feet from E Section Line
Lease Name: HEIDRICK Well #: 1
County: GREENWOOD Total Vertical Depth: 2103 feet

Operator License No.: 5394
Op Name: ABDERHALDEN, R. R.
Address: 100 S. MAIN, STE 510
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4	2170		0 SX
SURF	0	0		0 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/29/2014 10:00 AM
Plug Co. License No.: 5656 Plug Co. Name: R.R.A., INC.
Proposal Rcvd. from: DWAIN G. STOUT Company: Phone: (316) 640-9072

Proposed Plugging Method: In accordance with KCC regulations.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: PARTIAL
Date/Time Plugging Completed: 05/29/2014 1:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

ran tubing to 1134' pumped 25 sxs cement, pull tubing to 800' pumped 20 sxs cement, pull tubing to 250' pumped 75 sxs cement to surface, gel spacers between cement plugs.

RECEIVED

JUN 16 2014

KCC Chanute Dist. #3

mt

KCC WICHITA

JUN 23 2014

RECEIVED

Remarks:

Plugged through: TBG

District: 03


Signed

Milo Deffen
(TECHNICIAN)
6/25/14 ckm

810 E 7TH
PO Box 92
EUREKA, KS 67045
(620) 583-5561

Elite

**Cementing & Acidizing
of Kansas, LLC**



Cement or Acid Field Report

Ticket No. **1340**

Foreman STEVEN NEAL

Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
5-29-14	1046	Heidrik #1				Greenwood	Ks
Customer RRA Inc			Safety Meeting	Unit #	Driver	Unit #	Driver
Mailing Address 1005 Main St. Suite 510				104	Alan M		
City Wichita				110	Chris M		
State Ks				145	Alan G.		
Zip Code 67202							

Job Type PTA old well Hole Depth _____ Slurry Vol. _____ Tubing 2 3/8 1134'
Casing Depth _____ Hole Size _____ Slurry Wt. _____ Drill Pipe _____
Casing Size & Wt. _____ Cement Left in Casing _____ Water Gal/SK _____ Other _____
Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety meeting: Rig up to 2 3/8 tubing. Break circulation mix 350 # Gel
Spot 25 sks 60/40 Poz mix 4% Gel * Phenoseal. AT 1134'. Pull
tubing up to 800' Spot 20 sks 60/40 Poz mix 4% gel. Pull up tubing
up to 250' Pump 75 sks 250' to surface 60/40 Poz mix cement 4% Gel.
Pull out tubing Top well off Job complete Rig down

Thank you

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	750.00	750.00
C107	30	Mileage	3.95	118.50
C203	120 sks	60/40 Poz mix cement	12.75	1530.00
C206	400 #	Gel 4%	.20	80.00
C206	350 #	Gel spacer	.20	70.00
C113	2 1/2 hr	80 bbl track	85.00	212.50
C108A	5 1/2	ten mileage bulk track	m/c	345.00
			KCC WICHITA	
			JUN 23 2014	
			RECEIVED	
			Sub Total	3106.00
			Sales Tax 7.15%	222.08
Authorization <u>Daryl Whitman</u> Title _____			Total	3328.08

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.