

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-083-21896-00-00  
Spot: NWSWSENV Sec/Twnshp/Rge: 21-21S-23W  
2087 feet from N Section Line, 1552 feet from W Section Line  
Lease Name: BRADSHAW #1-21 Well #: 1  
County: HODGEMAN Total Vertical Depth: 4708 feet

Operator License No.: 33605  
Op Name: JOE GERSTNER OIL, LLC  
Address: PO BOX 509  
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
PC	5.5	1595		WITH 200 SX CMT
PROD	5.5	4697	0	WITH 170 SX CMT
SURF	12.25	218		WITH 175 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/16/2014 10:00 AM  
Plug Co. License No.: 32938 Plug Co. Name: NORTH FORK WELL SERVICE LLC  
Proposal Rcvd. from: JOE RUPP Company: JOE GERSTNER OIL LLC Phone: (785) 798-5151

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 50 SX CMT & 150# HULLS. PULL TBG TO 1600' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/16/2014 1:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4704' & SPOT 50 SX CMT & 150# HULLS. PULL TBG TO 1600' & PUMP 170 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4586	4596		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

KCC WICHITA

JUN 23 2014

RECEIVED

District: 01

Signed

*Michael Maier*  
6/26/14 CMM

(TECHNICIAN)

RECEIVED

JUN 18 2014

KCC DODGE CITY