

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-00767-00-00
Spot: SENWNW Sec/Twnshp/Rge: 7-30S-8W
990 feet from N Section Line, 990 feet from W Section Line
Lease Name: NIRSCHL B Well #: 2
County: KINGMAN Total Vertical Depth: 4320 feet

Operator License No.: 8740
Op Name: BRAMWELL PETROLEUM, INC.
Address: 12826 SW 77 AVE
ZENDA, KS 67159

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4319		150 SX
SURF	8.625	242		200 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/22/2014 12:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (620) 532-6019

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 05/16/2014 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 4068' - CAPPED WITH 5 SXS CEMENT ON TOP. PERFORATED @ 1350', 850' AND 295'. TUBING RAN INTO 1280' WITH PACKER ON END OF TUBING, PUMPED 35 SXS CEMENT. TAGGED TOP OF CEMENT AT 1280'. RAN TUBING INTO 750' WITH PACKER ON END OF TUBING, PUMPED 35 SXS CEMENT. COULD NOT TAG CEMENT, RAN TUBING INTO 850' PUMPED 40 SXS CEMENT WITH 100 LBS OF HULLS. TAGGED TOP OF CEMENT @ 663'. RAN TUBING INTO 300' CIRCUALTED TO SURFACE WITH 65 SXS CEMENT.

Perfs:

Top	Bot	Thru	Comments
4279	4314		
4258	4292		
4235	4241		
4221	4225		

Remarks: ALLIED CEMENTING OUT OF GREAT BEND, 60/40 4% POS MIX, TICKET #63937. PAST 10 YEAR TA.

Plugged through: TBG

District: 02

Signed

BJ Hope

6/26/14 ckm

(TECHNICIAN)

KCC WICHITA Form CP-2/3

JUN 26 2014

RECEIVED

JK