

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25143-00-00  
Spot: NWNESENW Sec/Twnshp/Rge: 25-12S-16W  
1475 feet from N Section Line, 2290 feet from W Section Line  
Lease Name: BRUNGARDT A Well #: 1  
County: ELLIS Total Vertical Depth: 3484 feet

Operator License No.: 3956  
Op Name: BRUNGARDT OIL AND LEASING INC.  
Address: 213 W. 7TH STREET PO BOX 871  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3484		250 SX
SURF	8.625	1022		400 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/13/2014 10:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: CHRISTOPHER BRUNGARD Company: BRUNGARDT OIL AND LEASING Phone: (785) 735-9405

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 11 sx gel and 500 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/13/2014 1:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 1600', 1225' and 600'.  
Ran tubing to 3050' and pumped 11 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1600' and pumped 125 sx cement. Pulled tubing to 350' and pumped 50 sx cement. Cement circulated out back side. Pumped an additional 100 sx cement and circulated it out the braden head. POOH. Hooked to casing and circulated out braden head. Shut in braden head and pressured casing to 300 psi to shut in.

GPS: 38.98319 -099.04961

Perfs:

Top	Bot	Thru	Comments
3192	3198		
3140	3142		

KCC WICHITA

JUN 26 2014

RECEIVED

Remarks: QUALITY CEMENTING TICKET # 450

Plugged through: TBG

District: 04

Signed

*Ray A. Dinkel*

6/26/14 *ckm*

(TECHNICIAN)

*CM*

JUN 17 2014