

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20744-00-01
Spot: S2NWNWNW Sec/Twnshp/Rge: 22-18S-13W
4290 feet from S Section Line, 1329 feet from W Section Line
Lease Name: TINDALL Well #: ↓
County: BARTON Total Vertical Depth: 1722 feet

Operator License No.: 6015
Op Name: CAMBRIA CORPORATION
Address: 3716 10TH ST PO BOX 1065
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	1721		50 SX
SURF	8.625	710		375 SX
T1	2.375	1604		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/12/2014 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: STEVE BODINE Company: CAMBRIA CORP. Phone: (620) 617-0876

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/12/2014 12:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1500' and 680'.
Ran tubing to 1610' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 700'.
Circulated cement to surface on casing w/140 sx cement. Pulled tubing. Circulated cement to surface on surface pipe with 60 sx cement.
GPS: 38.47538 -098.75171

Perfs:

Top	Bot	Thru	Comments
1709	1718		
1700	1702		
1646	1654		
1623	1634		
1595	1700		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

KCC WICHITA
JUN 26 2014
RECEIVED

District: 04

Signed Bruce Rodie
6/26/14 (TECHNICIAN)

CM

JUN 17 2014