

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21904-00-00
Spot: NWSWSESW Sec/Twnshp/Rge: 10-23S-22W
650 feet from S Section Line, 1580 feet from W Section Line
Lease Name: LUPFER Well #: 1-10
County: HODGEMAN Total Vertical Depth: 4470 feet

Operator License No.: 32331
Op Name: DK OPERATING INC.
Address: 621 BENTON ST.
JETMORE, KS 67854

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4440		WITH 2 SX CMT
COND	13.375	320		380 SX
PROD	5.5	4461	2992	WITH 75 SX CMT
SURF	8.625	1375		WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/18/2014 9:00 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: HAL HOSS Company: CHEYENNE WELL SERVICE, INC. Phone: (785) 798-2282

Proposed Plugging Method: SET CIBP @ 4440'. PLUG AT 1380' WITH 10 SX GEL & 50 SX CMT. PLUG AT 650' WITH 40 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE
Date/Time Plugging Completed: 06/18/2014 11:30 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

CIBP @ 4440' WITH 2 SX CMT. 1ST PLUG AT 1380' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 650' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT. TOP OFF WITH 10 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 01

RECEIVED
JUN 19 2014
KCC DODGE CITY

Signed

[Signature]
6/26/14
(TECHNICIAN)

KCC WICHITA
JUN 26 2014
RECEIVED