

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-171-21009-00-00  
Spot: SESENWNW Sec/Twnshp/Rge: 21-18S-31W  
4208 feet from S Section Line, 4159 feet from E Section Line  
Lease Name: JPB Well #: 1  
County: SCOTT Total Vertical Depth: 4700 feet

Operator License No.: 32158  
Op Name: H & B PETROLEUM CORP.  
Address: PO BOX 277  
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2908	0	WITH 380 SX CMT
SURF	8.625	437		WITH 250 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/20/2014 11:00 AM  
Plug Co. License No.: 34066 Plug Co. Name: TRINITY OILFIELD SERVICES INC.

Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed  
Plugging  
Method:

FILL CASING WITH CMT & 200# HULLS ON BOTTOM. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE  
Date/Time Plugging Completed: 06/20/2014 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

**\*\*CASING HAS BEEN CIRCULATED FROM 2900' TO SURFACE\*\* BULLHEADED THROUGH CASING. PUMPED 200# HULLS & 235 SX CMT. TOPPED OFF WITH 5 SX CMT. PUMPED 20 SX CMT DOWN THE BACKSIDE & PRESSURED UP.**

Remarks: USED 60/40 POZMIX 4% GEL BY GLOBAL CEMENTING

Plugged through: CSG

KCC WICHITA

JUN 26 2014

RECEIVED

District: 01

RECEIVED  
JUN 23 2014  
KCC DODGE CITY

Signed

Michael Maier  
6/26/14 CRM (TECHNICIAN)

Form CP-2/3