

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25151-00-01
Spot: NWSWNWSE Sec/Twnshp/Rge: 30-16S-22W
1785 feet from S Section Line, 2555 feet from E Section Line
Lease Name: JONES UNIT OWWO Well #: 1-30
County: NESS Total Vertical Depth: 4530 feet

Operator License No.: 5144
Op Name: MULL DRILLING COMPANY, INC.
Address: 1700 N WATERFRONT PKWY BLDG 12
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1623		CEMENTED WITH 160 SX CMT. 15 SX CMT CIRCULATED TO PIT
PROD	5.5	4514	0	WITH 150 SX CMT
SURF	8.625	217		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/18/2014 10:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: KYLE RANDA Company: MULL DRILLING Phone: (785) 798-3306

Proposed Plugging Method: PUMP 75 SX CMT & 300# HULLS ON BOTTOM. PUMP CMT FROM 1766' TO SURFACE. USE 50 SX CMT TO CHECK BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 06/18/2014 11:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMP 75 SX CMT & 250# HULLS ON BOTTOM. AT 1800' PUMPED 135 SX CMT TO SURFACE. CHECKED BACKSIDE WITH 5 SX CMT. PRESSURED TO 500#.

Perfs:

Top	Bot	Thru	Comments
4426	4430		
4422	4425		
4421	4428		
4338	4341		
4221	4428		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

KCC WICHITA

JUN 23 2014

RECEIVED

District: 01

RECEIVED

JUN 18 2014

KCC DODGE CITY

Signed

Michael Maier
6/26/14 CKM (TECHNICIAN)