

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-039-20793-00-00  
Spot: NESWNW Sec/Twnshp/Rge: 10-2S-27W  
1650 feet from N Section Line, 990 feet from W Section Line  
Lease Name: R WILSON Well #: 2-10  
County: DECATUR Total Vertical Depth: 3650 feet

Operator License No.: 31100  
Op Name: ROBUCK PETROLEUM., LLC  
Address: PO BOX 1896  
EDWARDS, CO 81632

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3624		470 SX
SURF	8.625	207		160 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/28/2014 9:30 AM  
Plug Co. License No.: 31660 Plug Co. Name: ROBUCK, DON E. DBA ENERGY SEARCH OPERATING COMPANY  
Proposal Rcvd. from: BRETT ROBUCK Company: ROBUCK PETROLEUM CO. LLC. Phone: (308) 340-3242

Proposed Plugging Method: 8 5/8" surface casing set at 207' w/160 sx cement. 4 1/2" production casing set at 3624' w/170 sx cement. TD-3650, PBTD-3501', Port collar set at 2098' w/300 sx cement. Cement did not circulate. Temperature survey indicated top of cement at 500'. Perforations: 3479' - 3483', 3443' - 3447' and 3354' - 3358'. Junk in hole. Topped off fish at 2900'. Anhydrite: 2076' - 2108'.  
Ordered 400 sx 60/40 pozmix 4% gel cement w/600 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/02/2014 9:30 AM KCC Agent: MARVIN MILLS

**Actual Plugging Report:**

Ran tubing to 2850' and pumped 40 sx cement with out hulls followed by 60 sx cement w/200 # hulls. Pulled tubing to 1950' and pumped 75 sx cement w/150 # hulls. Pulled tubing to 1000' and pumped 125 sx cement w/150 # hulls. Cement circulated to surface. Pulled tubing to surface. Cement pump truck experienced mechanical problems and could not finish plug job. 4 1/2" production casing and 8 5/8" surface pipe to be plugged ASAP.  
05/21/2014-Tied on to back side and squeezed with 65 sx full. Topped off casing with 15 sx full.

GPS: 39.89633 -100.34364

**Perfs:**

Top	Bot	Thru	Comments
3479	3483		
3443	3447		
3354	3358		

**KCC WICHITA**  
**JUN 25 2014**  
**RECEIVED**

Remarks: ENERGY SEARCH OPERATING COMPANY SERVICE RIG AND GLOBAL CEMENTING

Plugged through: TBG

District: 04

Signed [Signature]  
6/26/14 CRM (TECHNICIAN) CM

JUN 19 2014