

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-21943-00-00  
Spot: E2W2SESE Sec/Twnshp/Rge: 16-33S-6W  
660 feet from S Section Line, 700 feet from E Section Line  
Lease Name: CAROTHER BROTHERS A 330 Well #: 2-16  
County: HARPER Total Vertical Depth: 4940 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	4666		
PROD	5.5	4929		310 SX
SURF	8.625	745		355 SX
T1	2.875	4777		

Well Type: QG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/08/2014 12:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Revd. from: ALAN TIEDEMAN Company: TITAN WELL SERVICE Phone: (405) 828-4225

Proposed Plugging Method: Per KCC District Staff Instructions

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/10/2014 12:00 AM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

OPERATOR PLUGGED AND ABANDONED WELL. CIBP SET AT 4420' WITH TOOLS BELOW AND TAGGED. PLUG 1 WAS 35 SXS CLASS C SPOTTED @ 1075' AND TAGGED @ 940'. WELL CIRCULATED WIT H9 PPG MUD. PLUG 2 WAS 35 SKS CLASS C SPOTTED AT 800' AND TAGGED AT 675'. PLUG 3 WAS 55 SKS CLASS C SOTTED AT 60' TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4702	4712	CSG	
4460	4470	CSG	

Remarks: CEMENTING PERFORMED BY ALLIED OIL & GAS SERVICES, LLC MEDICINE LODGE, KS TICKET #62305

Plugged through: TBG

District: 02

Signed

*Ken Scofield*  
6/26/14 CKM (TECHNICIAN)

KCC WICHITA

JUN 26 2014

Form CP-2/3

RECEIVED