

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-20008-00-00
Spot: SENENW Sec/Twnshp/Rge: 26-22S-2W
4290 feet from S Section Line, 2970 feet from E Section Line
Lease Name: VOGT Well #: 1
County: HARVEY Total Vertical Depth: 3491 feet

Operator License No.: 30280
Op Name: SUNFLOWER WELL SERVICE, INC.
Address: 1770 28TH AVE PO BOX 341
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3490		225 SX
SURF	8.625	250		250 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/13/2014 12:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: BUD DAVIES Company: SUNFLOWER WELL SERVICE Phone: (620) 628-4723

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 05/15/2014 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3349' - CAPPED WITH 5 SXS CEMENT ON TOP. SET PLUG @ 2960' CAPPED WITH 5 SXS CEMENT, TAGGED TOP OF PLUG @ 2880'. PERFORATED AT 400' WITH 4 SHOTS, CIRCUALTED TO SURFACE WITH 250 SXS CEMENT.

Perfs:

Top	Bot	Thru	Comments
3398	3422		
2939	2968		

Remarks: COPELAND CEMENTING OUT OF BURRTON 60/40 4% POS MIX. TICKET #40842

Plugged through: CSG

District: 02

Signed BJ Hope
6/27/14 CKM (TECHNICIAN)

KCC WICHITA

Form CP-2/3

JUN 26 2014

RECEIVED

✓JK