

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-30009-00-01  
Spot: NWSENE Sec/Twnshp/Rge: 15-22S-15W  
4496 feet from S Section Line, 585 feet from E Section Line  
Lease Name: FERTIG B SWD (EOR) Well #: 2  
County: PAWNEE Total Vertical Depth: 3770 feet

Operator License No.: 5086  
Op Name: PINTAIL PETROLEUM, LTD.  
Address: 225 N MARKET STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3768	599	WITH 100 SX CMT
SURF	8.625	256		WITH 225 SX CMT

Well Type: EOR UIC Docket No: E18063.1 Date/Time to Plug: 05/29/2014 9:00 AM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: MIKE FRITZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: RTIH TO 3300' WITH 25 SX CMT & 200# HULLS. CUT CASING. PLUG AT 980' WITH 10 SX GEL & 50 SX CMT. PLUG AT 290' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: PARTIAL  
Date/Time Plugging Completed: 05/29/2014 5:00 PM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

RTIH TO 3312' & PUMPED 25 SX CMT WITH 200# HULLS. SHOT CASING AT 1450' & 1007'. COULDN'T RECOVER ANY CASING. 1ST PLUG AT 1003' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 290' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT. TOPPED OFF WITH 27 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3649	3750		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

Received  
KANSAS CORPORATION COMMISSION

JUN 06 2014

CONSERVATION DIVISION  
WICHITA, KS

District: 01

Signed

*Nathan Willis*  
6/19/14 (TECHNICIAN)

RECEIVED

JUN - 4 2014

KCC DODGE CITY

*cc to MC 6/10/14*

Form CP-2/3