

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19350-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 10-25S-3E
4365 feet from S Section Line, 1079 feet from E Section Line
Lease Name: ULMER Well #: 4
County: BUTLER Total Vertical Depth: 2740 feet

Operator License No.: 34569
Op Name: SONOMA RESOURCES LLC
Address: PO BOX 384
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2721		
PROD	5	2721		35 SX
PROD	5	2722		
SURF	10	90		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/22/2013 9:00 AM
Plug Co. License No.: _____ Plug Co. Name: _____
Proposal Rcvd. from: DAN FLOWERS/SONOMA R Company: SONOMA RESOURCES Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: _____ WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/22/2013 9:00 AM KCC Agent: PATRICK SHIELDS

Actual Plugging Report:

RAN TUBING TO BOTTOM AND CLEANED OUT HOLE. PULLED TUBING AND DROPPED SAND. RAN TUBING TO BOTTOM AND PUMPED 30 SXS OF 60X40 POZ (<4% GEL). PULLED TUBING AND TAGGED BOTTOM PLUG AT 2430'. DUG OUT HEAD TO EXPOSE LARGE CASING, PERFORATED AT 250'. RAN TUBING TO 250' AND CIRCULATED CEMENT BETWEEN 5" AND 10". RAN 1" TUBING DOWN BACKSIDE TO 250' AND BROUGHT CEMENT TO SURFACE. TOTAL TOP PLUG = 250 SXS. TOPPED OFF WITH 75 SXS OF CLASS A ON 7/24/13.

Perfs:


Top	Bot	Thru	Comments
2710	2740		

Remarks: PLUGGED DUE TO COMPLIANCE. NO ACTIVE LEASE.

Plugged through: TBG

District: 02

Signed


6/19/14
(TECHNICIAN)

KCC WICHITA

JUN 02 2014

Form CP-2/3

RECEIVED