

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-25847-00-00  
Spot: NENWSW Sec/Twnshp/Rge: 8-19S-15W  
2310 feet from S Section Line, 990 feet from W Section Line  
Lease Name: BARTON Well #: 1  
County: BARTON Total Vertical Depth: 3781 feet

Operator License No.: 30337  
Op Name: SPECIAL ENERGY CORP.  
Address: PO DRAWER 369  
STILLWATER, OK 74076

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3800	1938	200 SX
SURF	8.625	1023		375 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/22/2014 8:00 AM  
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.  
Proposal Rcvd. from: DON NOLAN Company: SPECIAL ENERGY CORP. Phone: (405) 880-5437

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/22/2014 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped off with cement. Cut casing at 1935'. Pulled casing to 1650' and pumped 125 sx cement w/200 # hulls. Pulled casing to 1100' and pumped 60 sx cement w/100 # hulls. Pulled casing to 448'. Circulated cement to surface with 140 sx cement. Pulled casing and topped off with 40 sx cement.

GPS: 38.41238 -099.01122

Perfs:

Top	Bot	Thru	Comments
3640	3646		

KCC WICHITA

MAY 21 2014

RECEIVED

Remarks: ALLIED CEMENTING TICKET # 62916

Plugged through: CSG

District: 04

Signed Bruce Rodie  
6/19/14 (TECHNICIAN)

CM

APR 29 2014

Form CP-2/3