

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-03801-00-00  
Spot: NESWSESW Sec/Twnshp/Rge: 9-17S-11W  
495 feet from S Section Line, 3465 feet from E Section Line  
Lease Name: GROSSARDT K Well #: 3  
County: BARTON Total Vertical Depth: 3271 feet

Operator License No.: 7757  
Op Name: FOLK, MAX LEE DBA FOLK OIL  
Address: 604 N. BISMARCK AVE  
ELLINWOOD, KS 67526

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD   | 6.625 | 3269       |             | 250 SX   |
| SURF   | 10.75 | 319        |             | 250 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/15/2014 8:00 AM  
Plug Co. License No.: 34032 Plug Co. Name: SIEMSEN WELL SERVICE INC.  
Proposal Rcvd. from: MAX FOLK Company: FOLK OIL Phone: (785) 252-3300

Proposed Plugging Method: Junk in well at 2350'. Will plug from there.  
Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/16/2014 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perforated at 1450', 685' and 300'. Ran tubing to 2300' and pumped 150 sx cement w/200 # hulls. Pulled tubing to 1450' and pumped 125 sx cement w/200 # hulls. Pulled tubing to 700' and pumped 370 sx cement w/100 # hulls. No cement returns. Pulled tubing. Will tag cement on 05/16/14.  
05/16/14- Tagged cement at 730'. Pulled one joint of tubing to 700'. Circulated cement to surface with 125 sx cement. Pulled tubing and topped off casing with 20 sx cement. Pressured to 500 psi and shut in. Hooked to surface pipe backside pressured to 1500 psi.

GPS: 38.58116 -098.54715

Remarks: ALLIED CEMENTING TICKET # 63604

Plugged through: T&E  
ESC

KCC WICHITA

MAY 21 2014

RECEIVED

District: 04

Signed Bruce Rodie  
6/17/14 (TECHNICIAN)

CM

MAY 19 2014