

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-21186-00-01  
Spot: NESW Sec/Twnshp/Rge: 6-14S-12W  
1980 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: WAYMASTER Well #: 1  
County: RUSSELL Total Vertical Depth: 3400 feet

Operator License No.: 34674  
Op Name: H & D EXPLORATION LLC  
Address: 165 WEST 1ST PO BOX 387  
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	03399	0	w/150sx
SURF	8.625	045'	0	w/180sx

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/13/2014 2:30 PM  
Plug Co. License No.: 34147 Plug Co. Name: ACE WELL SERVICE, INC.  
Proposal Rcvd. from: GERALD ACHATZ Company: H & D EXPLORATION Phone: (620) 282-9086

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/13/2014 6:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3000' and pumped 75 sx cement. Pulled tubing to 1880' and pumped 75 sx cement. Pulled tubing to 760' and pumped 60 sx cement. Cement circulated out back side. POOH. Hooked to casing and pumped 25 sx cement. Pressured up to 200 psi. Hooked to braden head and pumped 50 sx cement. Pressured up to 250 psi to shut in.

GPS: 38.86176 -098.69949

Perfs:

Remarks: QUALITY CEMENTING SERVICE TICKET # 181

Plugged through: CSG

KCC WICHITA

MAY 28 2014

RECEIVED

District: 04

Signed

Ray Dinkel  
6/17/14

(TECHNICIAN)

CM

MAY 19 2014

Form CP-2/3