

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-23060-00-00
Spot: NESWNWSE Sec/Twnshp/Rge: 25-30S-12W
1841 feet from S Section Line, 2036 feet from E Section Line
Lease Name: 99 SPRINGS Well #: 1
County: BARBER Total Vertical Depth: 4870 feet

Operator License No.: 33186
Op Name: LB EXPLORATION, INC.
Address: 2135 2ND RD
HOLYROOD, KS 67450

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 3500 | | WITH 4 SX CMT |
| CIBP | | 3800 | | |
| PROD | 4.5 | 3957 | 2370 | WITH 125 SX CMT |
| SURF | 8.625 | 293 | | WITH 230 SX CMT |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/19/2014 4:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SET CIBP @ 3500' & 2 SX CMT. PLUG AT 680' WITH 10 SX GEL & 50 SX CMT. PLUG AT 320' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: PARTIAL
Date/Time Plugging Completed: 05/19/2014 5:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3500' & PUT 4 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 690' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 320' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3816 | 3820 | | |
| 3544 | 3549 | | |

KCC WICHITA
MAY 30 2014
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIZ 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

RECEIVED

MAY 21 2014

KCC DODGE CITY

Signed

Stephen Pfeifer
6/17/14
(TECHNICIAN)

Form CP-2/3