

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-09910-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 25-19S-13W
3630 feet from S Section Line, 4950 feet from E Section Line
Lease Name: WOOD Well #: 4
County: BARTON Total Vertical Depth: 3470 feet

Operator License No.: 32638
Op Name: NADEL AND GUSSMAN LLC
Address: 15 E 5TH ST STE 3200
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3470		125 SX
SURF	8.625	380		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/18/2014 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: DUANE WOOD Company: NADEL & GUSSMAN Phone: (785) 737-3051

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls and 15 sx gel.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/18/2014 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1350', 680' and 350'. Ran tubing to 3387' and pumped 15 sx gel followed by 75 sx cement w/100 # hulls. Pulled tubing to 1350' and pumped 70 sx cement w/100 # hulls. Pulled tubing to 700' and pumped 40 sx cement w/100 # hulls. Pulled tubing to 350'. Circulated cement to surface with 60 sx cement on casing and 120 sx cement on surface pipe. Pulled tubing and hole stayed full.
GPS: 38.37175 -098.71755

Perfs:

Top	Bot	Thru	Comments
3418	3420		
3171	3345		

Remarks: COPELAND ACID AND CEMENTING
Plugged through: ESG

KCC WICHITA
MAY 21 2014
RECEIVED

District: 04

Signed Bruce Rodie
6/19/14 (TECHNICIAN) CM

APR 19 2014
APR 29 2014