

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-21254-00-00
Spot: SWSE Sec/Twnshp/Rge: 13-33S-30W
660 feet from S Section Line, 1980 feet from E Section Line
Lease Name: EVANS Well #: 1
County: MEADE Total Vertical Depth: 6500 feet

Operator License No.: 34242
Op Name: OOLITE ENERGY CORP
Address: PO BOX 9398
AMARILLO, TX 79105

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5740		WITH 2 SX CMT
CIBP		6045		
PROD	5.5	6484	2533	WITH 185 SX CMT
SURF	8.625	1647		WITH 520 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 05/21/2014 12:00 PM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: CIBP @ 5740' WITH 2 SX CMT. PLUG AT 1680' WITH 10 SX GEL & 50 SX CMT. PLUG AT 570' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: DANIEL SELLERS Witness Type: NONE
Date/Time Plugging Completed: 05/21/2014 5:00 PM KCC Agent: DANIEL SELLERS

Actual Plugging Report:

CIBP @ 5740' WITH 2 SX CMT. 1ST PLUG AT 1680' WITH 10 SX GEL & 50 SX CMT.
2ND PLUG AT 570' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6067	6078		
5885	5889		
5851	5856		
5800	5809		
5795	5798		
5790	5793		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

KCC WICHITA

MAY 27 2014

RECEIVED

District: 01

Signed

Daniel Sellers
6/12/14

(TECHNICIAN)

RECEIVED

MAY 22 2014

KCC DODGE CITY

Form CP-2/3