

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-21311-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 33-17S-7W
2310 feet from N Section Line, 330 feet from W Section Line
Lease Name: KNIFFIN Well #: 1
County: ELLSWORTH Total Vertical Depth: 3520 feet

Operator License No.: 5146
Op Name: RAINS & WILLIAMSON OIL CO., INC.
Address: 220 W DOUGLAS STE 110
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	293		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/08/2014 11:00 AM

Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.

Proposal Rcvd. from: _____ Company: DUKE DRILLING CO., INC. Phone: _____

Proposed Plugging Method: 35 SXS @ TOP ARBUCKLE, 35 SXS @ 1050', 35SXS @ 650', PULL TO 60', AND CIRCUALTE. 30 SXS IN RATHOLE, 20 SXS IN MOUSEHOLE, 60X40 <4% GEL.

Plugging Proposal Received By: JEFF KLOCK

WitnessType: NONE

Date/Time Plugging Completed: 05/08/2014 11:00 AM

KCC Agent: PATRICK SHIELDS

Actual Plugging Report:

Perfs:

35 SXS @ 3471' (TOP OF ARBUCKLE). 35 SXS @ 1050' (BOTTOM OF SALT). 35 SXS @ 650' (TOP OF SALT). 35 SXS @ 343' (50' BELOW SURFACE CASING). PULLED TO 60' AND CIRCUALTE TO SURFACE. 30 SXS IN RATHOLE, 20 SXS IN MOUSEHOLE, 60X40 <4% GEL.


Remarks: DRY HOLE

Plugged through: DP

KCC WICHITA
MAY 23 2014
RECEIVED

District: 02

Signed



(TECHNICIAN)

JK