

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-23424-00-00  
Spot: NESESWNW Sec/Twnshp/Rge: 31-16S-24W  
3070 feet from S Section Line, 4160 feet from E Section Line  
Lease Name: MATTHEWS Well #: 3  
County: NESS Total Vertical Depth: 4519 feet

Operator License No.: 5215  
Op Name: PHILLIPS, LEE E. DBA LEE PHILLIPS OI  
Address: 151 WHITTIER STE 1400  
WICHITA, KS 67207

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4514	0	WITH 350 SX CMT
SURF	8.625	312		WITH 220 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/20/2014 9:00 AM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: GARY HORCHEM Company: WHITETAIL CRUDE Phone: (785) 731-5312

Proposed Plugging Method: PUMP 150# HULLS & 30 SX CMT ON BOTTOM. CIRCULATE CMT TO SURFACE FROM 1880'. CHECK BACKSIDE.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/20/2014 12:30 PM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

\*\*ALTERNATE II COMPLETED 2/19/90 BY PERFORATING 4 1/2" CASING AT 1100' & CIRCULATING CMT TO SURFACE WITH 140 SX CMT.\*\* BOTTOM PLUG AT 4450' WITH 150# HULLS & 30 SX CMT. RUN IN WITH TBG TO 1880' & CIRCULATED CMT TO SURFACE WITH 185 SX CMT. PULLED TBG & TOPPED OFF WITH 15 SX CMT. BACKSIDE HELD AT 300 PSI. TOOK NO CMT. GOOD RETURNS DURING PUMPING.

Perfs:

Top	Bot	Thru	Comments
4507	4508		

KCC WICHITA  
MAY 27 2014

RECEIVED-

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed

*Nathan Willis*  
6/19/14 (TECHNICIAN)

RECEIVED

MAY 21 2014

KCC DODGE CITY