

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22035-00-01
Spot: NWSWSENE Sec/Twnshp/Rge: 26-16S-13W
2974 feet from S Section Line, 1055 feet from E Section Line
Lease Name: KOELLER Well #: 1
County: BARTON Total Vertical Depth: 3745 feet

Operator License No.: 6988
Op Name: SMITH, RICHARD E. DBA SMITH OIL O
Address: 410 N. ADAMS PO BOX 550
HUTCHINSON, KS 67504

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 4.5 | 3743 | | 125 SX |
| SURF | 8.625 | 330 | | 190 SX |

Well Type: SWD UIC Docket No: D20922.0 Date/Time to Plug: 04/11/2014 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: DALE R OHL Company: SMITH OIL OPERATION Phone: (620) 663-6622

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/200 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/11/2014 9:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

04/11/2014- Sanded back to 3500' and spotted 5 sx cement on top. Dug out braden head and found it to be full of cement.
04/14/2014- Ran tubing to 2520' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 1004' and pumped 65 sx cement w/100 # hulls. Cement circulated to surface. POOH and pumped 10 sx cement to top off.

GPS: 38.63197 -098.72363

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3605 | 3625 | | |

KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING TICKET # 40008

Plugged through: TBG

APR 23 2014

RECEIVED

District: 04

Signed Ray A. Dinkel (TECHNICIAN)

CM