

3 055095

To:

STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-003-22207 · 00  
SW 1/4 Sec/Twp/Rge 16-22-19E  
1540 feet from south section line  
3300 feet from east section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 9362  
Operator: WILLIAMS GAS PIPELINE CNT  
Name & 19209 SW MARYLAND RD  
Address WELDA KS 66091

Lease/Well# BOOTS #9 35.00  
County ANDERSON  
Well Total Depth 860.5 feet  
Production Pipe: 2 7/8 Size Feet 863  
Surface Casing: 7 Size Feet 20  
AB oil well XXXX Gas Well \_\_\_\_\_ SWD Well/ Input Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereinafter indicated:

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SVC INC Lic. # 6372  
Address: P. O. BOX 386 / CHANUTE KS 66720

Company to plug at: Hour: 1:00 Day: 26 Month: 9 2000

Plugging proposal received from: BERNIE ROCKERS

Company Name: WILLIAMS GAS PIPELINE CNT Phone: 785-448-4816

Were:

863' OF 2 7/8" PIPE CEMENTED TO SURFACE  
PUMP 2 7/8" PIPE FULL WITH CEMENT AND SHUT WELL IN

Plugging Proposal Received by: T J WELSH

Plugging attended by Agent: All XXXX Part \_\_\_\_\_  
TECHNICIAN  
None \_\_\_\_\_

Operations Completed: Hour: 2:00 Day: 26 Month: 9 2000

Actual Plugging Report:

HOOKED ONTO 2 7/8" PIPE SQUEEZED 35 SX CEMENT SHUT WELL IN @900 PSI

RECEIVED  
STATE CORPORATION COMMISSION

OCT 24 2000

10-24-00

CONSERVATION DIVISION  
Wichita, Kansas

Remarks:

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

INVOICED  
Signed: \_\_\_\_\_  
DATE 10/24/00  
WV. NO. 2001060873

Thomas J Welsh  
TECHNICIAN

State of Kansas  
NOTICE OF INTENTION TO DRILL

API Number 15-003-22, 207  
 Sec, Sec 16 T 22 S, R 19  
 1540 ft. from N or S line of section  
 1980 ft. from W or E line of section

Starting date 5/21/83  
 Operator license # 6080

Operator name & address  
 R #1  
 WELDA, K.S. 66091  
 CLYDE BOOTS  
 Boots Oil Co.

Contact person  
 Phone 316 852 3574  
 5913

Contractor license # 5913  
 ALCO DRILLING CO. INC.

Contractor name & address  
 R #3  
 101A, K.S. 66749

Type equipment: rotary \* air cable  
 Well drilled for: oil \* gas SWD

Inf. class: OWO  
 Well class: infld \* poll ext - wildcat

I certify that we will comply with K.S.A. 55-101, et seq., plus originally plugged holes to KCC specs.  
 Signature of operator or agent  
 Date 5-11-83  
 \$40 Fee Paid PC # 6649  
 Date received 5-16-83

To be filed with Kansas Corporation Commission  
 5 days prior to commencing well.  
 Card to be typed

Form C-1  
 MHC-HOME 5/16/83  
 2-25-83  
 2-25-83

Nearest lease or unit boundary line 660 feet  
 County ANDERSON  
 Lease name BOOTS  
 Surface piped by alternate 1 or 2 \*  
 Depth of fresh water NONE feet  
 Lowest usable water formation NONE feet  
 Depth to bottom of usable water 1080 feet MSL  
 Surface pipe to be set 20 feet  
 Conductor pipe if any required NONE feet  
 Est. total depth 850 feet  
 Into solid formation not less than 20 ft

THIS PERMIT  
 NOV 10 1983  
 EXPIRES

2-25-83  
 11:30 pm  
 East

**KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 S. Market - Room 2078  
Wichita, Kansas 67202**

**WELL PLUGGING RECORD**

K.A.R.-82-3-117

**RECEIVED**  
STATE CORPORATION COMMISSION

OCT 20 2000

API NUMBER 15-003-22207 • 00 - 00  
LEASE NAME BOOTS  
WELL NUMBER 9  
1540 Ft. from S Section Line  
3300 Ft. from E Section Line

CONSERVATION DIVISION  
Wichita, Kansas

LEASE OPERATOR WILLIAMS GAS PIPELINES CENTRAL SEC. 16 TWP. 22 RGE. 19 E  
ADDRESS 19209 SW MARYLAND RD./ WELDA, KS. 66091 COUNTY ANDERSON  
PHONE # 785-448-4816 OPERATORS LICENSE # 09362 DATE WELL COMPLETED 5/28/83  
CHARACTER OF WELL OIL PLUGGING COMMENCED 9/26/00  
(Oil Gas D&A SWD Input Water Supply Well) PLUGGING COMPLETED 9/26/00  
THE PLUGGING PROPOSAL WAS APPROVED ON 9/15/00 (DATE)  
BY TOM WELSH (KCC DISTRICT AGENT'S NAME).  
IS ACO-1 FILED? N/A IF NOT, IS WELL LOG ATTACHED? YES

PRODUCING FORMATION SQUIRREL DEPTH TO TOP 835' BOTTOM 840' T.D. 860.5'  
SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS		CASING RECORD				
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SQUIRREL	OIL	- 0 -	20'	7"	20'	- 0 -
		- 0 -	863'	2 7/8"	863'	- 0 -

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED, STATE THE CHARACTER OF SAME AND DEPTH PLACED, FROM \_\_\_ FEET TO \_\_\_ FEET EACH SET.


TIED TO 2 7/8" - SQUEEZED 35 SACKS OF PORTLAND CEMENT INTO WELL FROM TOP TO BOTTOM - SHUT WELL IN WITH 900# OF BACK PRESSURE.

(IF ADDITION DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR SPLAIN PULLING AND ROUSTABOUT SERVICE, INC. LICENSE NO. 6372  
ADDRESS P.O. BOX 386 / CHANUTE, KS. 66720  
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES WILLIAMS GAS PIPELINES CENTRAL  
STATE OF KANSAS COUNTY OF ANDERSON, ss.

(Employee of Operator) or (Operator) of

Above-described well, being first duly sworn on oath, says: that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.




(Signature) Bernard Roebuck  
(Address) 19209 SW Maryland Rd. - Welda, KS. 66091  
SUBSCRIBED AND SWORN TO before me this 18<sup>th</sup> Day of October, 20 00  
Jody L. Troyer  
Notary Public

My Commission Expires: 8-20-2001

*(Handwritten initials)*

Louis McClain, President  
Dean Michael, Vice-President

Iola, Kansas  
Telephone: 316-365-6013



# Alco Drilling Co., Inc.

ROTARY DRILLING CONTRACTORS  
Plugging, Work-Over & Fishing Service

RURAL ROUTE 3  
IOLA, KANSAS 66749

Well Log  
Boots No. 9  
Anderson County Kansas

0	7	Soil & clay
7	34	Lime
34	46	Shale
46	115	Lime
115	238	Shale
238	273	Lime
273	301	Shale
301	306	Lime
306	352	Shale
352	410	Lime
410	416	Shale
416	436	Lime
436	441	Shale
441	458	Lime w/shale
458	467	Shale w/lime
467	654	Shale w/ lime streaks
654	672	Lime w/shale
672	709	Shale w/sandy shale
709	731	Shale
731	740	Lime
740	756	Shale
756	760	Lime
760	780	Shale
780	786	Lime
786	796	Shale
796	806	Shale
806	833	Shale w/lime
833	834 $\frac{1}{2}$	Lime
834 $\frac{1}{2}$	839 $\frac{1}{2}$	Sand good odor
839 $\frac{1}{2}$	864	Shale