

TO:-
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21204-00-00
Spot: SWNE Sec/Twnshp/Rge: 27-34S-16W
2085 feet from N Section Line, 2085 feet from E Section Line
Lease/Unit Name: MURDOCK-OXY Well Number: 1-27
County: COMANCHE Total Vertical Depth: 5850 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

Conductor Pipe: Size feet: 190.13
Surface Casing: Size 13.375 feet: 325 WITH 250 SX CMT
Production: Size 5.5 feet: 5845 WITH 200 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/25/2002 9:30 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: CIBP @ 5475' & 2 SX CMT. 1ST PLUG AT 700' WITH 15 SX GEL - 50 SX CMT. 2ND PLUG AT 350' WITH 125 SX CMT. 3RD PLUG AT 40' WITH 35 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 06/25/2002 10:45 AM

KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 5805'. PERFS AT 5528-5532'. SET CIBP @ 5475' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 700' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 350' WITH 125 SX CMT. 3RD PLUG AT 40' WITH 35 SX CMT.

RECEIVED

JUL 03 AM
7-3-02
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3180' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

JUL 01 2002

DATE

7-8-02

INV. NO.

2003060005

Form 5/2/3

15-033-21204-0000

ALLIED CEMENTING CO., INC.

P.O. BOX 31
RUSSELL, KS 67665
PH (785) 483-3887
FAX (785) 483-5566
FEDERAL TAX ID# 48-0727860

I N V O I C E

Invoice Number: 087497

Invoice Date: 06/27/02

RECEIVED

JUL 01 2002

RECEIVED

JUL 2 2002
7-2-02
KCC WICHITA

Sold Murfin Drilling Co.
To: 250 N. Water, St. #300
Wichita, KS
67202

Cust I.D.....: Murfin
P.O. Number...: MurdockOxyI-22
P.O. Date.....: 06/27/02

Due Date.: 07/27/02
Terms.....: Net 30

RA 36/RK

Item I.D./Desc	Qty	Used	Unit	Price	Net	TX
Common	135.00		SKS	6.6500	897.75	T
Pozmix	100.00		SKS	3.5500	355.00	T
Gel	27.00		SKS	10.0000	270.00	T
Handling	252.00		SKS	1.1000	277.20	T
Mileage (45)	45.00		MILE	10.0800	453.60	T
252 sks @\$.04 per sk per mi						
Plug	1.00		JOB	475.0000	475.00	T
Mileage pmp trk	45.00		MILE	3.0000	135.00	T

All Prices Are Net, Payable 30 Days Following	Subtotal:	2863.55
Date of Invoice. 1 1/2% Charged Thereafter.	Tax.....:	183.27
If Account CURRENT take Discount of \$ <u>286.36</u>	Payments:	0.00
ONLY if paid within 30 days from Invoice Date	Total....:	3046.82

15-033-21284-0000

ALLIED CEMENTING CO., INC. 09874

Federal Tax I.D.# 48-0727860

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Medicine Lodge

DATE <u>6-25-02</u>	SEC. <u>27</u>	TWP. <u>34s</u>	RANGE <u>16W</u>	CALLED OUT <u>7:00 Am</u>	ON LOCATION <u>8:30 Am</u>	JOB START <u>9:30 Am</u>	JOB FINISH <u>10:45 Am</u>
LEASE <u>Murdock - oxy</u>		WELL # <u>1-27</u>	LOCATION <u>Buttermilk Body Shop, Inc</u>		COUNTY <u>Comanche</u>	STATE <u>Ks</u>	
OLD OR NEW (Circle one)			<u>15, 14, 3/5</u>				

CONTRACTOR <u>Mikes TFS</u>	OWNER <u>Murfin Drilling Co.</u>
TYPE OF JOB <u>OHP</u>	
HOLE SIZE <u>7 7/8</u>	T.D.
CASING SIZE <u>13 7/8</u>	DEPTH <u>340'</u>
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX <u>150</u>	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	
PERFS.	
DISPLACEMENT <u>Fresh</u>	
EQUIPMENT	
PUMP TRUCK CEMENTER <u>Carl Balding</u>	
# <u>362-281</u> HELPER <u>Steve David</u>	
BULK TRUCK	
# <u>364</u> DRIVER <u>Robert L.</u>	
BULK TRUCK	
#	DRIVER

CEMENT			
AMOUNT ORDERED			
<u>250 sx 60:40:6% Gal (used 277 sx)</u>			
<u>15 sx Gal</u>			
COMMON <u>A</u>	<u>135</u>	@ <u>6.65</u>	<u>897.75</u>
POZMIX	<u>100</u>	@ <u>3.55</u>	<u>355.00</u>
GEL	<u>27</u>	@ <u>10.00</u>	<u>270.00</u>
CHLORIDE		@	
		@	
		@	
		@	
		@	
		@	
		@	
		@	
HANDLING <u>252</u>		@ <u>1.10</u>	<u>277.20</u>
MILEAGE <u>252</u> X <u>45</u>		@ <u>.04</u>	<u>453.60</u>
			TOTAL <u>2253.55</u>

RECEIVED

JUL 2 2002
7-2-02
KCC WICHITA

REMARKS:

1st plug 700' load hole w/ 15 sx Gal + Pump 50 sx cement

2nd plug 350' load hole w/ freshwater + Pump 125 sx cement

3rd plug Pump 50 sx 40' to surface

DEPTH OF JOB <u>700'</u>		
PUMP TRUCK CHARGE		<u>475.00</u>
EXTRA FOOTAGE	@	
MILEAGE <u>45</u>	@ <u>3.00</u>	<u>135.00</u>
PLUG	@	
	@	
	@	
TOTAL <u>610.00</u>		

CHARGE TO: Murfin Drilling Co.

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

	@	
	@	
	@	
	@	
	@	
TOTAL _____		

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX <u>183.27</u>	
TOTAL CHARGE <u>3046.82</u>	
DISCOUNT <u>286.36</u>	IF PAID IN 30 DAYS
<u>2760.46</u>	
PRINTED NAME	

SIGNATURE Monte J Paduca

COPY