

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-20811-00-01
Spot: SENWNWNW Sec/Twnshp/Rge: 11-16S-26W
4930 feet from S Section Line, 4833 feet from E Section Line
Lease Name: SNYDER Well #: 1
County: NESS Total Vertical Depth: 4567 feet

Operator License No.: 5144
Op Name: MULL DRILLING COMPANY, INC.
Address: 1700 N WATERFRONT PKWY BLDG 12
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		2071		
PROD	4.5	4544	0	WITH 100 SX CMT
SURF	8.625	246		WITH 175 SX CMT

Well Type: SWD UIC Docket No: D19878.0 Date/Time to Plug: 06/04/2014 8:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: KYLE RANDA Company: MULL DRILLING Phone: (316) 264-6366

Proposed Plugging Method: RUN TBG TO 1750'. PUMP CMT WITH HULLS TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: NATHAN WILLIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/04/2014 11:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

DV TOOL @ 2071'. PBD @ 2050'. RAN TBG TO 1700'. PUMPED 115 SX CMT WITH 150# HULLS, CIRCULATING CMT TO SURFACE. PULLED TBG & TOPPED OFF WITH 15 SX CMT. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 200#.

Remarks: USED SMD CMT BY SWIFT SERVICES.

Plugged through: TBG

Received
KANSAS CORPORATION COMMISSION

JUN 11 2014

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed

(TECHNICIAN)

RECEIVED

JUN -6 2014

KCC DODGE CITY

Form CP-2/3