

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-21024-00-00
Spot: S2SWSENE Sec/Twnshp/Rge: 23-5S-30W
2550 feet from N Section Line, 990 feet from E Section Line
Lease Name: ANNA Well #: 1-23
County: DECATUR Total Vertical Depth: 4166 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4155		125 SX
SURF	8.625	219		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/21/2014 8:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (800) 962-1206

Proposed Plugging Method: PC at 2591' w/170 sx cement
Production perforations: 3819' - 4012'
Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls

Plugging Proposal Received By: DARREL DIPMAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/21/2014 12:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3799'. Swift pumped 8 sx gel followed by 100 sx cement w/300 # hulls. Pulled tubing to 2532' and pumped 125 sx cement w/300 # hulls. Pulled tubing to 1267' and pumped 125 sx cement. Cement circulated. PTOH and topped off 5 1/2" casing w/20 sx cement. Hooked to backside with instant pressure.

Perfs:

Top	Bot	Thru	Comments
4004	4012		
3968	3973		
3886	3891		

Remarks: SWIFT CEMENTING TICKET # 25547

Plugged through: TBG

District: 04

Signed Richard Williams
6/17/14 (TECHNICIAN)

CM

MAY 27 2014

KCC WICHITA
JUN 05 2014
RECEIVED