

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20515-00-00
Spot: NWNW Sec/Twnshp/Rge: 28-3S-36W
4620 feet from S Section Line, 4620 feet from E Section Line
Lease Name: CELIA SOUTH UNIT Well #: B5
County: RAWLINS Total Vertical Depth: 4742 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4742		285 SX
SURF	8.625	344		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/30/2014 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 462-6781

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls and 8 sx gel.
PC at 3144' w/550 sx cement.
Production perforations: 4694' - 4702'.

Plugging Proposal Received By: DARREL DIPMAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/30/2014 1:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 4644' and pumped 8 sx gel followed by 100 sx cement w/225 # hulls. Pulled tubing to 3126' and pumped 150 sx cement w/300 # hulls. Pulled tubing to 1548' and pumped 160 sx cement to circulate cement to surface. Pulled all tubing and topped off 5 1/2" casing w/25 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pumped 15 sx cement. Shut in pressure 150 psi.

GPS: 39.76950N -101.37015W

Perfs:

Top	Bot	Thru	Comments
4694	4702		

Remarks: SWIFT TICKET # 26653

Plugged through: TBG

KCC WICHITA

JUN 12 2014

RECEIVED

District: 04

Signed

Pat Bedore
6/12/14 (TECHNICIAN)

CM

JUN 04 2014